



Roxby Landfill – Residents Update

December 2019

Biffa

Roxby Landfill



Engineering Works

Residents of Roxby & Winterton

I would like to make you aware of the revised engineering works that we first informed you of in November 2019. Recent heavy rainfall in Lincolnshire has led to more difficult operating conditions than usual at our Roxby site. We are putting extra measures in place to address this which have been submitted to the Environment Agency who visited the site on the 3rd December. We also have a meeting with councillors from all local parishes to discuss these actions and ongoing plans.

To date a total 74 gas extraction pin wells have been installed and are now under extraction. A further 50 to 60 pin wells are currently being installed along eastern and northern perimeters of the site with an additional 500m of horizontal gas pipework being placed in the operational area. To ensure these works are completed before the Christmas break additional teams of contractors have been mobilised.

During these works we will endeavour to control any odours with the installation of additional portable de odouriser units and enhancing the static perimeter mobile system. All the drilled sections will also be capped and sealed at the end of each operational day to prevent any associated odours escape.

Further permanent capping works are planned to commence in the New Year once all the planned additional gas infrastructure is installed and operational. In the interim inert materials will continue to be used to act as temporary capping.

I would like to thank you in advance for your patience during these improvements works, as always, we strive to ensure we adhere to regulations and respect the local environments where we operate

Kind Regards

James Harrison, Roxby Site Manager
james.harrison@biffa.co.uk / 01724 733 336